

STANDARD NOTES

- AB ABANDON. IF APPLIED TO CONDUIT, REMOVE CONDUCTORS.
- BC INSTALL PULL BOX IN EXISTING CONDUIT RUN.
- CB INSTALL CONDUIT INTO EXISTING PULL BOX.
- CC CONNECT NEW AND EXISTING CONDUIT. REMOVE EXISTING CONDUCTORS AND INSTALL CONDUCTORS AS INDICATED.
- CF CONDUIT TO REMAIN FOR FUTURE USE. REMOVE CONDUCTORS. INSTALL PULL WIRE OR ROPE.
- DH DETECTOR HANDHOLE.
- MT CONDUIT WITH PULL WIRE OR ROPE.
- PEU PHOTOELECTRIC UNIT.
- R REMOVE EQUIPMENT.
- RS REMOVE AND SALVAGE EQUIPMENT
- RI REMOVE EXISTING CONDUCTORS. INSTALL NEW CONDUCTORS AS INDICATED.
- RL RELOCATE EQUIPMENT.
- RR REMOVE AND REUSE EQUIPMENT.
- SC SPLICE NEW TO EXISTING CONDUCTORS.

ABBREVIATIONS (CON'T)

- DMS DYNAMIC MESSAGE SIGN
- E EXISTING TO REMAIN
- EMS EXTINGUISHABLE MESSAGE SIGN
- FB FLASHING BEACON
- HPS HIGH PRESSURE SODIUM
- COM TRAFFIC SIGNAL COMMUNICATIONS CABLE
- LED LIGHT EMITTING DIODE
- LPS LOW PRESSURE SODIUM
- PB PULL BOX
- PEC PHOTOELECTRIC CONTROL
- PED PEDESTRIAN
- PEU PHOTOELECTRIC UNIT
- PGS PARKING GUIDANCE SIGN
- PPB PEDESTRIAN PUSH BUTTON
- PT POST TOP
- R REMOVE (TO BECOME PROPERTY OF CONTRACTOR)
- RRFB RAPID RECTANGULAR FLASHING BEACON
- S SALVAGE (DELIVER TO CSJ)
- SNS STREET NAME SIGN
- SP SERVICE POINT
- TSP TRANSIT SIGNAL PRIORITY
- UNO UNLESS NOTED OTHERWISE
- USO UNLESS SPECIFIED OTHERWISE
- WP WEATHER PROOF
- XFMR TRANSFORMER

ABBREVIATIONS

- APS AUDIBLE/ACCESSIBLE PEDESTRIAN SIGNAL (AS IDENTIFIED ON SCHEDULE)
- C CONSTRUCT. SUPPLIED AND INSTALLED BY CONTRACTOR, UNLESS SPECIFIED OTHERWISE.
- CKT CIRCUIT
- CMS CHANGEABLE MESSAGE SIGN
- CSJ INSTALLED BY CITY
- DLC LOOP DETECTOR LEAD IN CABLE

APPROVED BY  
  
 DATE  
 4-20-19

TRAFFIC SIGNAL AND STREETLIGHTING  
 NOTES AND ABBREVIATIONS

DEPARTMENT OF PUBLIC WORKS



DRAWING  
 NO.  
 E-01a